

ABSTRAK

RANCANGAN *THREE MONTHS ROLLING PLAN SEQUENCE* PIT SITARUM PT BINUANG MITRA BERSAMA BLOK DUA KALIMANTAN SELATAN

Oleh
Fadhilah Afifah
NIM: 112210028
(Program Studi Sarjana Teknik Pertambangan)

Perencanaan jangka pendek yang disusun dalam bentuk *Three Months Rolling Plan* (TMRP) diperlukan untuk menjamin kelancaran kegiatan produksi tambang sesuai sasaran perusahaan. *Three Months Rolling Plan* (TMRP) *Three months rolling plan* merupakan bagian dari rencana jangka pendek yang merupakan bagian perbaikan desain dari triwulan atau juga bisa disebut dengan suatu rencana yang mencakup perencanaan pen

ABSTRACT

RANCANGAN *THREE MONTHS ROLLING PLAN SEQUENCE* PIT SITARUM PT BINUANG MITRA BERSAMA BLOK DUA KALIMANTAN SELATAN

By
Fadhilah Afifah
NIM: 112210028
(Mining Engineering Undergraduated Program)

A Three Months Rolling Plan (TMRP) is a short term plan essential for ensuring the smooth execution of mining production activities and meeting company targets. The TMRP is a detailed, short-term plan and an improved version of a quarterly design. It provides a detailed mining plan for the first month, with the following two months planned concurrently. This research was conducted at Pit Sitarum, PT Binuang Mitra Bersama Blok Dua, located in South Kalimantan. The objective was to design a three month mining sequence based on reserve analysis and the calculation of mechanical